

NBS SPECIFICATION CLAUSE FOR KWIK-KLIK ULTRASPAN (EXTERNAL USE) – 01.02.12

Q40 Fencing

To be read with Preliminaries/ General conditions.

FENCING SYSTEMS

430 PROPRIETARY FENCING: TEMPORARY HOARDING

- Manufacturer: **Kwik-Klik Hoardings Limited**
10-14 Ward Street, Bradford, West Yorkshire, BD7 3PR
Telephone: 01274 535 660 Email: tony@kwik-klik.co.uk
www.kwik-klik.co.uk www.ecogenik.com

Product reference: **Ultraspan**

- Height: 2.3m to 6m+ (unlimited)
- Materials: Extruded PVC Vertical Panels.
 - Panel Sizes: 407mm x 10mm / 250mm X 10mm
 - Finish: White / Grey / Blue / Custom
- Support System: Timber Framework / Steel Post System /
- Accessories: Printed Images / Printed Logos

EXECUTION

710 INSTALLATION GENERALLY

- Set out and erect:
 - Alignment: Straight lines or smoothly flowing curves.
 - Tops of posts: Following profile of the ground.
 - Setting posts: Rigid, plumb and to specified depth, or greater where necessary to ensure adequate support.
 - Fixings: All components securely fixed.

715 COMPETENCE

- Operatives: Contractors must employ competent operatives.

720 SETTING POSTS IN CONCRETE

- Standard: To BS 8500-2.
- Mix: Designated concrete not less than GEN1 or Standard prescribed concrete not less than ST2.
- Alternative mix for small quantities: 50 kg Portland cement to 150 kg fine aggregate to 250kg 20mm nominal maximum size coarse aggregate, medium workability.
- Admixtures: Do not use.
- Holes: Excavate neatly and with vertical sides.
- Filling: Position post/ strut and fill hole with concrete to not less than the specified depth, well rammed as filling proceeds and consolidated.
- Backfilling of holes not completely filled with concrete: Excavated material, well rammed and consolidated.

730 EXPOSED CONCRETE FOUNDATIONS

- Filling: Compact until air bubbles cease to appear on the upper surface.
- Finishing: Weathered to shed water and trowelled smooth.

740 SETTING POSTS IN EARTH

- Holes: Excavated neatly, with vertical sides and as small as practicable to allow refilling.
- Filling: Position posts/ struts and replace excavated material, well rammed as filling proceeds.

750 DRIVEN POSTS

- Damage to heads: Minimise.
Repair: Neatly finish post tops after installation.

760 NAILED WOOD RAILS

- Length (minimum): Two bays, with joints in adjacent rails staggered.
- Fixing: Nail each length of rail to each post with two 100mm galvanised nails.
- Rails with split ends: Replace.

COMPLETION

910 CLEANING

- General: Leave the works in a clean, tidy condition.
- Surfaces: Clean immediately before handover.